2022-27 MS4 General Permit Ordinance Change Checklist -	Data of Charling ClC/2024	
Option 1 embed standards in your ordinance  Purpose of Checklist: This checklist was developed by the Southern Maine Stormwater Working Group and	Date of Checklist: 6/6/2021	
the Interlocal Stormwater Working Group to assist Planners and Planning Boards in updating ordinances to		
reflect the requirements of the 2022 General Permit (GP) for Stormwater Discharges from Small Municipal		
Separate Storm Sewer Systems (MS4) dated 10/15/2020, and to consider related optional recommendations		
from the 2020 Maine Climate Council (MCC) and the 2017 Maine Municipal Climate Adaptation Series		
(MCAS).		
(*************************************		
	Existing Municipal Ordinance or Policy	
2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control	Requirements (provide citation either summary or	
Requirements for "ordinance or other regulatory mechanism"	quote of existing requirement)	Recommended Changes or additions
,	· · · · · ·	
MS4 Permittee must implement: "An ordinance or other regulatory mechanism that requires the		
use of erosion and sediment control best management practices (BMPs) at construction sites		
consistent with the minimum standards outlined in Appendix C, Erosion and Sedimentation		
Control, Inspections and Maintenance and Housekeeping of this GP. Also see the Department's		
website for a guidance document entitled Maine Erosion and Sediment Control Practices Field		
Guide For Contractors to assist contractors and municipalities in developing BMPs for the		
ordinance or other regulatory mechanism. Permittees who have an existing ordinance must		
evaluate the ordinance and update it as needed within one (1) year of the effective date of this GP		
(7/1/2023) to provide the permittee with the necessary enforcement authority. Those permittee's		
without an existing ordinance must develop an ordinance within one (1) year (7/1/2023) of the		
effective date of this GP and have an approved ordinance in place with the necessary enforcement		
· · · · · · · · · · · · · · · · · · ·		
authority within two (2) years (7/1/2024) of the effective date of this GP."		
Threshold: Erosion and Sediment Control BMPs must be used at construction sites which disturb		
one or more acres of land, and at smaller sites that are part of a larger common plan of		
development or sale that would disturb one acre or more.  MCAS (Site Plan Review) Recommendation: Include a smaller threshold: any site which results in		
square feet of new impervious cover. (MCAS recommends using 2,000 square feet within a 3-		
year period).		

2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control Requirements for "ordinance or other regulatory mechanism"	Existing Municipal Ordinance or Policy Requirements (provide citation either summary or quote of existing requirement)	Recommended Changes or additions
MCAS (Site Plan Review) Recommendation: Require that the Erosion and Sediment Control Plan be prepared by a Maine-licensed professional engineer or CPESC and implemented in accordance with Maine Erosion and Sediment Control BMPs, Maine Department of Environmental Protection, (October 2016 or most current version), that describes and shows the locations, elevations, installation schedule and construction or planting details of all proposed pre- and post-construction erosion and sediment control measures. (Note municipalities may want to replace requirement to use a PE or CPESC with some standard BMPs for small sites).  Design all BMPs in accordance with precipitation data from the Northeast Regional Climate Center website (http://precip.eas.cornell.edu), Extreme Precipitation Tables. Maine DEP Chapter 500 requires use of these data tables.  OR  Design all BMPs in accordance with precipitation data from the NOAA Atlas 14 tables (https://hdsc.nws.noaa.gov/hdsc/pfds/pfds_map_cont.html). MCAS recommends use of NOAA Atlas 14 precipitation data.		
	_	

	Existing Municipal Ordinance or Policy	
2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control	Requirements (provide citation either summary or	
Requirements for "ordinance or other regulatory mechanism"	quote of existing requirement)	Recommended Changes or additions
MS4 REQUIRED APPENDIX C: EROSION & SEDIMENT CONTROL		-
Erosion and sediment control measures must be in place before construction activity begins. Measures must		
remain in place and functional until the site is permanently stabilized. Adequate and timely maintenance and		
temporary and permanent stabilization measures must be taken.		
Applicant shall request a pre-construction meeting 10 days before construction activity begins. (added		
10/26/2021)		
Applicant shall provide notice of permanent stabilization to allow for final municipal inspection. (added		
10/26/2021)		
1. Pollution Prevention: Minimize disturbed areas and protect natural downgradient buffer areas, and any		
areas where stormwater may flow off-site to the extent practicable. Control stormwater volume and velocity		
within the site to minimize soil erosion. Minimize the disturbance of steep slopes. Control stormwater		
discharges, including both peak flow rates and volume, to minimize erosion at outlets. The discharge may not		
result in erosion of any open drainage channels, swales, stream channels or stream banks, upland, or coastal or		
freshwater wetlands off the project site.		
Whenever practicable, no disturbance activities should take place within 50 feet of any protected natural		
resource. If disturbance activities take place between 30 feet and 50 feet of any protected natural resource,		
and stormwater discharges through the disturbed areas toward the protected natural resource, perimeter		
erosion controls must be doubled. If disturbance activities take place less than 30 feet from any protected		
natural resource, and stormwater discharges through the disturbed areas toward the protected natural resource, perimeter erosion controls must be doubled and disturbed areas must be temporarily or permanently		
stabilized within 7 days, or before the next rain event, whichever comes sooner.		
If it is not practicable to maintain the 50-foot buffer of no disturbance, the ESC Plan must include redundant (at		
least two) perimeter control measures that are appropriate for the soil and slope.		
reast two/ permieter control measures that are appropriate for the son and stope.		
<b>2. Sediment barriers:</b> Prior to construction, properly install sediment barriers at the downgradient edge of any		
area to be disturbed and adjacent to any drainage channels within the disturbed area. Sediment barriers		
should be installed downgradient of soil or sediment stockpiles and stormwater must be prevented from		
running onto the stockpile. Maintain the sediment barriers by removing accumulated sediment, or removing		
and replacing the barrier, until the disturbed area is permanently stabilized. Where a discharge to a storm		
drain inlet occurs, you must install and maintain protection measures that remove sediment from the		
discharge. Storm drain inlet protection must include effective curb inlet or "back throat" protection, where		
applicable.		
3. Stabilized construction entrance: Prior to construction, properly install a stabilized construction entrance		
(SCE) at all points of egress from the site. The SCE is typically a stabilized pad of aggregate, underlain by a		
geotextile filter fabric, or an engineered track out control mat which has been approved by Maine DEP; which		
is used to prevent traffic from tracking material away from the site onto public ROWs. Maintain the SCE until		
all disturbed areas are stabilized. If an engineered track out control mat has been approved by Maine DEP,		
provide proof of this with the Plan or application. (added 10/26/2021)		
4. Temporary stabilization: Within 7 days of the cessation of construction activities in an area that will not be		
worked for more than 7 days, stabilize any exposed soil with mulch, or other non-erodible cover. Stabilize		
areas within 75 feet of a wetland or waterbody within 48 hours of the initial disturbance of the soil or prior to		
any storm event, whichever comes first.		

	Existing Municipal Ordinance or Policy	
2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control	Requirements (provide citation either summary or	
Requirements for "ordinance or other regulatory mechanism"	quote of existing requirement)	Recommended Changes or additions
5. Removal of temporary measures: Remove any temporary control measures, such as silt fence, within 30	quote of existing requirement/	The commended endinger of additions
days after permanent stabilization is attained. Remove any accumulated sediments and stabilize.		
6. Permanent stabilization: If the area will not be worked for more than one year or has been brought to final		
grade, then permanently stabilize the area within 7 days by planting vegetation, seeding, sod, or through the		
use of permanent mulch, or riprap, or road sub-base. If using vegetation for stabilization, select the proper		
vegetation for the light, moisture, and soil conditions; amend areas of disturbed subsoils with topsoil, compost,		
or fertilizers; protect seeded areas with mulch or, if necessary, erosion control blankets; and schedule sodding,		
planting, and seeding so to avoid die-off from summer drought and fall frosts. Newly seeded or sodded areas		
must be protected from vehicle traffic, excessive pedestrian traffic, and concentrated runoff until the		
vegetation is well-established with 90% cover by healthy vegetation. If necessary, areas must be reworked		
and restabilized if germination is sparse, plant coverage is spotty, or topsoil erosion is evident. Permanent		
Stabilization Definitions are as follows:		
a. Seeded areas. For seeded areas, permanent stabilization means a 90% cover of the disturbed area with		
mature, healthy plants with no evidence of washing or rilling of the topsoil.		
b. Sodded areas. For sodded areas, permanent stabilization means the complete binding of the sod roots into		
the underlying soil with no slumping of the sod or die-off.		
c. Permanent mulch. For mulched areas, permanent mulching means total coverage of the exposed area with		
an approved mulch material. Erosion Control Mix may be used as mulch for permanent stabilization according		
to the approved application rates and limitations.		
d. Riprap. For areas stabilized with riprap, permanent stabilization means that slopes stabilized with riprap		
have an appropriate backing of a well-graded gravel or approved geotextile to prevent soil movement from		
behind the riprap. Stone must be sized appropriately. It is recommended that angular stone be used.		
e. Paved areas. For paved areas, permanent stabilization means the placement of the compacted gravel		
subbase is completed, provided it is free of fine materials that may runoff with a rain event		
f. Ditches, channels, and swales. For open channels, permanent stabilization means the channel is stabilized		
with a 90% cover of healthy vegetation, with a well-graded riprap lining, turf reinforcement mat, or with		
another non-erosive lining such as concrete or asphalt pavement. There must be no evidence of slumping of the		
channel lining, undercutting of the channel banks, or down-cutting of the channel.		
7. Winter construction: "Winter construction" is construction activity performed during the period from		
November 1 through April 15. If disturbed areas are not stabilized with permanent measures by November 1		
or new soil disturbance occurs after November 1, but before April 15, then these areas must be protected and		
runoff from them must be controlled by additional measures and restrictions.		
a. Site stabilization: For winter stabilization, hay mulch is applied at twice the standard temporary		
stabilization rate. At the end of each construction day, areas that have been brought to final grade must be		
stabilized. Mulch may not be spread on top of snow.		
b. Sediment barriers: All areas within 75 feet of a protected natural resource must be protected with a double		
row of sediment barriers.		
c. Ditch: All vegetated ditch lines that have not been stabilized by November 1, or will be worked during the		
winter construction period, must be stabilized with an appropriate stone lining backed by an appropriate		
gravel bed or geotextile unless specifically released from this standard by the Department. If release from		
Maine DEP has been granted, provide proof of this with the Plan or application.		
d. Slopes: Mulch netting must be used to anchor mulch on all slopes greater than 8% unless erosion control		
blankets or erosion control mix is being used on these slopes.		

	Existing Municipal Ordinance or Policy	
2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control	Requirements (provide citation either summary or	
Requirements for "ordinance or other regulatory mechanism"	quote of existing requirement)	Recommended Changes or additions
8. Stormwater channels: Each channel should be constructed in sections so that the section's grading, shaping,		
and installation of the permanent lining can be completed the same day. If a channel's final grading or lining		
installation must be delayed, then diversion berms must be used to divert stormwater away from the channel,		
properly-spaced check dams must be installed in the channel to slow the water velocity, and a temporary		
lining installed along the channel to prevent scouring.		
9. Sediment basins: Sediment basins that will be used to control sediment during construction activities must		
be designed to provide storage for either the calculated runoff from a 2-year, 24-hour storm or provide for		
3,600 cubic feet of capacity per acre draining to the basin. Outlet structures must discharge water from the		
surface of the basin whenever possible. Erosion controls and velocity dissipation devices must be used if the		
discharging waters are likely to create erosion. Accumulated sediment must be removed as needed from the		
basin to maintain at least ½ of the design capacity of the basin. Clearly visible staking must be installed with		
marks showing the elevation of 1/2 design capacity for easier inspection.		
The use of cationic treatment chemicals, such as polymers, flocculants, or other chemicals that contain an		
overall positive charge designed to reduce turbidity in stormwater may only be used if proof of approval by		
Maine Department of Environmental Protection is provided.		
10. Phasing Plan requirements: No phasing plan is required if contractor will limit disturbance to a maximum of		
5 acres of disturbance across the entire project at any time. If the site will result in more than 5 acres of		
disturbance at any one time, the contractor will provide a phasing plan showing:		
a. the initial 5 acre area to be disturbed		
b. which portions of the initial disturbance will be stabilized, and what temporary or permanent stabilization		
methods will be used		
c. which areas will be subsequently disturbed and what temporary or permanent stabilization methods will be		
used.		
d. each phase of disturbance and stabilization will clearly show the total areas in square feet or acres such that		
the 5-acre disturbance limit at any one time is met throughout the entire project.		
MS4 REQUIRED APPENDIX C: INSPECTION & MAINTENANCE		

	Existing Municipal Ordinance or Policy	
2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control	Requirements (provide citation either summary or	
Requirements for "ordinance or other regulatory mechanism"	quote of existing requirement)	Recommended Changes or additions
1. During construction		
a. Inspection & corrective action: Inspect disturbed and impervious areas, erosion control measures, materials		
storage areas that are exposed to precipitation, and locations where vehicles enter or exit the site. Inspect		
these areas at least once a week as well as before and within 24 hours after a storm event (rainfall), and prior		
to completing permanent stabilization measures. A person with knowledge of erosion and stormwater control,		
including the standards and conditions in the permit, shall conduct the inspections. (Submittal requirements		
shall include example inspection form to be used by applicant - added 10/26/2021).		
<u>b. Maintenance:</u> If best management practices (BMPs) need to be repaired or enhanced, the repair work should		
be initiated upon discovery of the problem but no later than the end of the next workday. If additional BMPs or		
significant repair of BMPs are necessary, implementation must be completed within 7 calendar days and prior		
to any storm event (rainfall). All measures must be maintained in effective operating condition until areas are		
permanently stabilized.		
c. Documentation: Keep a log (report) summarizing the inspections and any corrective action taken. The log		
must include the name(s) and qualifications of the person making the inspections, the date(s) of the inspections,		
and major observations about the operation and maintenance of erosion and sedimentation controls, materials		
storage areas, and vehicles access points to the parcel. Major observations must include BMPs that need		
maintenance, BMPs that failed to operate as designed or proved inadequate for a particular location, and		
location(s) where additional BMPs are needed. For each BMP requiring maintenance, BMP needing		
replacement, and location needing additional BMPs, note in the log the corrective action taken and when it		
was taken. Maintain records for at least three years from the completion of permanent stabilization.		
MS4 REQUIRED APPENDIX C: HOUSEKEEPING		
1. Spill prevention: Controls must be used to prevent pollutants from construction and waste materials stored		
on site to enter stormwater, which includes storage practices to minimize exposure of the materials to		
stormwater. The site contractor or operator must develop, and implement as necessary, appropriate spill		
prevention, containment, and response planning measures.		
NOTE: any spill of toxics/HazMat's must be reported to DEP.		
2. Groundwater protection: During construction, liquid petroleum products and other hazardous materials with		
the potential to contaminate groundwater may not be stored or handled in areas of the site draining to an		
infiltration area. An "infiltration area" is any area of the site that by design or as a result of soils, topography		
and other relevant factors accumulates runoff that infiltrates into the soil. Dikes, berms, sumps, and other		
forms of secondary containment that prevent discharge to groundwater may be used to isolate portions of the		
site for the purposes of storage and handling of these materials. Any project proposing infiltration of		
stormwater must provide adequate pre-treatment of stormwater prior to discharge of stormwater to the		
infiltration area, or provide for treatment within the infiltration area, in order to prevent the accumulation of		
fines, reduction in infiltration rate, and consequent flooding and destabilization.		
3. Fugitive sediment & dust: Actions must be taken to ensure that activities do not result in noticeable erosion of soils or fugitive dust emissions during or after construction. Oil may not be used for dust control, but other		
water additives may be considered as needed. A stabilized construction entrance (SCE) should be included to		
minimize tracking of mud and sediment. If off-site tracking occurs, public roads should be swept immediately		
and no less than once a week and prior to significant storm events. Operations during dry months, that		
experience fugitive dust problems, should wet down unpaved access roads once a week or more frequently as		
needed with a water additive to suppress fugitive sediment and dust.		

	Existing Municipal Ordinance or Policy	
2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control	Requirements (provide citation either summary or	
Requirements for "ordinance or other regulatory mechanism"	quote of existing requirement)	Recommended Changes or additions
Requirements for oraniance of other regulatory mechanism	quote of existing requirement)	Recommended changes of additions
4. Debris & other materials: Minimize the exposure of construction debris, building and landscaping materials,		
trash, fertilizers, pesticides, herbicides, detergents, sanitary waste and other materials to precipitation and		
stormwater runoff. These materials must be prevented from becoming a pollutant source. Sediment generated		
by concrete or mortar mixing, brick cutting & saw cutting activities must be contained (e.g.: Sausage boom,		
straw bales, etc.) and cleaned up using dry methods (i.e.: Sweeping or vacuuming) to prevent it from entering		
drainage structures or water resources. These activities should be done on vegetated areas whenever		
possible and away from drainage structures and water resources.		
NOTE: may require compliance with other DEP provisions (hazmat, solid waste, oil conveyance, etc.)		
5. Excavation dewatering: Excavation de-watering is the removal of water from trenches, foundations, coffer		
dams, ponds, and other areas within the construction area that retain water after excavation. In most cases		
the collected water is heavily silted and hinders correct and safe construction practices. The collected water		
removed from the ponded area, either through gravity or pumping, must be spread through natural wooded		
buffers or otherwise treated to collect the maximum amount of sediment possible, like a cofferdam		
sedimentatin basin. Avoid allowing the water to flow over disturbed areas of the site. If the Maine DEP has		
approved equivalent measures, provide proof of approval. Note that discharge of excavation de-water fluids		
from the site must be visually clear (no visible suspended or settleable solids).		
NOTE: refer to dewatering controls in DEP ESC BMP guidance documents		
6. Authorized Non-SW discharges: Identify and prevent contamination by non-stormwater discharges. Where		
allowed non-stormwater discharges exist, they must be identified and steps should be taken to ensure the		There is some available with the New Champanatan
implementation of appropriate pollution prevention measures for the non-stormwater component(s) of the		There is some overlap with the Non-Stormwater
discharge. Authorized non-stormwater discharges are:		Discharge Ordinance here, but that list needs to
a. Discharges from firefighting activity;		be updated to include the following missing items:
b. Hydrant flushing if dechlorinated to 0.05 mg/l or less		c. Vehicle wash water w/out detergents and no
c. Vehicle wash water if detergents are not used and washing is limited to the exterior of vehicles (engine,		engine/undercarriage
undercarriage and transmission washing is prohibited);		d. Dust control per (C)(3)
d. Dust control runoff if it does not cause erosion		e. External building washdown w/out detergents
e. Routine external building washdown, not including surface paint removal, that does not involve detergents;		j. Uncontaminated excavation dewatering per
f. Pavement wash water (where spills/leaks of toxic or hazardous materials have not occurred, unless all spilled		(C)(5)
material had been removed) if detergents are not used;		(6)(3)
g. Uncontaminated air conditioning or compressor condensate		or the full list should be repeated for the
h. Uncontaminated groundwater or spring water		construction standards with a reference to the
i. Foundation or footer drain-water where flows are not contaminated		Non-Stormwater Discharge Ordinance.
j. Uncontaminated excavation dewatering per item 5 Excavation Dewatering		Tell of this area bisonarge of unique.
k. Potable water including waterline flushings		
I. Landscape irrigation		
7. Unauthorized non-SW discharges: following discharges are prohibited		
a. Wastewater from the washout or cleanout of concrete, stucco, paint, form release oils, curing compounds or		
other construction materials		The section of the se
b. Fuels, oils or other pollutants used in vehicle and equipment operation and maintenance;		These items are covered by the NSDO, but may
c. Soaps, solvents, or detergents used in vehicle and equipment washing; and		want to explicitly list these out as prohibited by
d. Toxic or hazardous substances from a spill or other release.		construction operations.

Т	Existing Municipal Ordinance or Policy	
2022-27 MS4 General Permit - MCM 4 - Construction Site Stormwater Runoff Control	Requirements (provide citation either summary or	
Requirements for "ordinance or other regulatory mechanism"	quote of existing requirement)	Recommended Changes or additions
8. Washout from concrete, stucco, paint, curing compounds or other construction materials: If	,	,
washout/cleanout is to be completed on Site, a designated area(s) shall be established and marked on the		
Erosion and Sediment Control Plan. This area shall be a minimum of 50 feet from all drainage structures,		
ditches, waterbodies, and resource areas, as well as property boundaries. The area shall not have an outlet to		
discharge wastes or flows. No detergents shall be used or vehicles washed in this location. A leak-proof pit or		
container shall be established in the washout area(s), to which washings shall be directed. This area shall be		
used for washout containment and dewatering by evaporation only. The pit shall not allow infiltration to		
occur. To prevent clean water from entering the pit, the washout area shall be covered during precipitation		
events. Inspections of the pit shall be conducted daily to ensure no leaks are present and no discharge is		
occurring. (added 2/8/2022)		
9. Additional requirements: may be required on site-specific basis		
Additional Ordinance related Requirements		
MS4 - MCM 4 4.a.iv: Sediment and Erosion Control Plan must include waste control procedures for: discarded		These items are already listed in items 1 and 7
building materials, concrete washout, chemicals, litter & sanitary waste		above.
MS4 - MCM 5 Post Construction Stormwater Ordinance must require that the owner or operator of a post		
construction BMP provide the permittee with an annual report completed by a qualified inspector documenting		
that all BMPs are adequately maintained and functioning as intended.  MS4 - MCM 5 Post Construction Stormwater Ordinance - must require that if a post construction BMP needs		
maintenance, the owner or operator must document the deficiency and either correct it within 60 days of		
discovery or establish an expeditious schedule to correct it.		
MS4 Common audit finding: Urbanized Area Definition should reference the cumulative Urbanized Area	+	
defined by the 2000 and 2010 Census.		
defined by the 2000 and 2010 census.	+	
	_	
Additional non-ordinance related MCM4 Requirements		
4.a.ii: site plan review procedures incorporating WQ impacts, EC, waste storage and ability for public comment		
4.a.iii: site developer/operator notification procedures for MCGP & Ch500 registration		
4.a.v: construction activity documentation for 1ac or more disturbance		
a. Written site inspection & enforcement procedures of ESC BMPs with clearly defined responsibilities for		
inspection & enforcement which must include imposition of sanctions to ensure compliance.		
b. Inspections:		
i. Min 3 inspections during active earth-moving construction phase		
ii. Min 1 inspection annually until project completion		
iii. 1 of 3 inspections must be at project completion to verify permanent stabilization & removal of all		
temporary ESC BMPs iv. Documentation of inspections, enforcement actions & corrective actions		
IV. Documentation or inspections, enforcement actions & corrective actions		
Credits: This checklist was prepared by SMPDC, CCSWCD, and Integrated Environmental Engineering, Inc.	<u></u>	
Under award CZM NA20NOS4190064 to the Maine Coastal Program from the National Oceanic and	noar Integrated	CUMBERLAND COUNTY
Atmospheric Administration, U.S. Department of Commerce. The statements, findings, conclusions, and	Environmental	SOIL & WATER
recommendations are those of the author(s) and do not necessarily reflect the views of NOAA or the	SMPDC ENGINEERIN	CONSERVATION DISTRICT
Department of Commerce.	E II WILL E E II I	